N5242A-02

S E R V I C E N O T E

Supersedes: none

Model Number: N5242A

Model Name: PNA-X Network Analyzer

Serial Numbers: MY47420368 / 9999Z99999

Front Panel Touch Screen Handling Procedure to prevent touch screen from damage.

Parts Required:

This service note is intended to highlight safe handling procedures for the PNA-X touch screen. No parts are required.

ADMINISTRATIVE INFORMATION

SERVICE NOTE CLASSIFICATION:	
INFORMATION ONLY	
AUTHOR: [initials] PY	PRODUCT LINE: WN
ADDITIONAL INFORMATION:	

© AGILENT TECHNOLOGIES, INC. 2008 PRINTED IN U.S.A.



Page 1 of 3

April 21, 2008

Rev. 14

Page 2 of 3 N5242A-02


Situation:

Front panel touch screen can fail to operate. Failure analysis found cables which broke due to excessive handling.


Solution/Action:

Careful handling the touch screen is required to prevent it from malfunctioning. Please refer to the touch screen handling procedure below.

Front Panel Touch Screen Assembly & Handling Procedure: The Do's and Don'ts




Never lay down the touch screen with the cable folded under. This will create a crease in the cable and fracture the conductors within the cable.



Never lay down the touch screen with the cable folded under. This will create a crease in the cable and fracture the conductors within the cable.

Page 3 of 3 N5242A-02

DON'T PULL



Must never handle or pull the touch screen up from the Front Frame by using the cable. The cable is very fragile and can cause the traces to fracture.





Always lift up the frame and push the touch screen from the bottom in order to remove it from the front frame.

